



KARACHI PORT TRUST
GATEWAY TO PAKISTAN
CIVIL WORKS DIVISION



PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA)
CONTRACT AWARD PROFORMA-I
(As Per Rule-47 of PP Rules, 2004)

To Be Filled and Uploaded on PPRA Website in Respect of All Public Contracts of Works, Services and Goods.

- NAME OF THE ORGANIZATION / DEPARTMENT. **Karachi Port Trust / Civil Works Division**
- FEDERAL / PROVINCIAL GOVT. **Federal Govt. (KPT Board of Trustees)**
- TITLE OF CONTRACT **CONSTRUCTION OF TWO NUMBER SITTING ROOMS WITH 05 BATHROOMS AT TPX AREAS, KARACHI.**
- TENDER NUMBER **TS500170E Dated 13-01-2023**
- BRIEF DESCRIPTION OF CONTRACT: Traffic Manager and Commandant (PSF) vide their letters has requested for provision of 02 Staff Office alongwith Washroom & 03 separate Washroom at different locations of TPX Area, as at present, no such type of facility exists and the staff is facing difficulties for the same.
- TENDER VALUE **Rs. 4,770,085.95**
- ENGINEER'S ESTIMATE (for civil Works only) **Rs. 3,843,240.00**
- ESTIMATED COMPLETION PERIOD **06 Months**
- WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN? **NO**

➤ Advertisement: i) PPRA Website (Federal Agencies) (If yes, give date and PPRA's tender number) • Dated: 13-01-2023 • PPRA No. TS500170E ii) News Papers (If yes, give names of newspapers and dates)	Yes	No
	✓	
	Yes	No
		✓
➤ TENDER OPENED ON (DATE & TIME)	30-01-2023 at 1100 Hrs.	
➤ NATURE OF PURCHASE	Local	Int.
	✓	
➤ EXTENSION IN DUE DATE (If any)	Yes	No
		✓

Executive Engineer (W)
Engineering Department
Karachi Port Trust

➤	NUMBER OF TENDER DOCUMENTS SOLD	Not Known Uploaded on PPRA / KPT Websites	
➤	WHETHER QUALIFICATION CRITERIA WAS INCLUDED IN BIDDING/TENDER DOCUMENTS (If yes enclose a copy).	Yes	No
		✓	
➤	WHETHER BID EVALUATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS (If yes enclose a copy).	Yes	No
		✓	
➤	WHICH METHOD OF PROCUREMENT WAS USED: - (Tick one)		
	a) SINGLE STAGE - ONE ENVELOPE PROCEDURE _____		✓
	b) SINGLE STAGE - TWO ENVELOPE PROCEDURE _____		-
	c) TWO STAGE BIDDING PROCEDURE _____		-
	d) TWO STAGE - TWO ENVELOPE BIDDING PROCEDURE _____		-
➤	PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED WITH BRIEF REASONS (i.e. EMERGENCY, DIRECT CONTRACTING, NEGOTIATED TENDERING ETC.)	N/A	
➤	WHO IS THE APPROVING AUTHORITY	<u>Bord's Sanction</u>	
➤	WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A METHOD OTHER THAN OPEN COMPETITIVE BIDDING.	Yes	No
			✓
➤	NUMBER OF BIDS RECEIVED	Three Bids Received	
➤	WHETHER THE SUCCESSFUL BIDDER WAS LOWEST BIDDER	Yes	No
		✓	
		Three Bids Received	
➤	WHETHER INTEGRITY PACT WAS SIGNED	Yes	No
			✓


Executive Engineer (EP)
Engineering Department
Karachi Port Trust

PUBLIC PROCUREMENT REGULATORY AUTHORITY (PPRA)

(As Per Rule-47 of PP Rules, 2004)



CONTRACT AWARD PROFORMA –II

**To Be Filled And Uploaded on PPRA Website in Respect of All
Public Contracts of Works, Services & Goods**

➤	NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS	Two (02) Nos.
➤	NAME AND ADDRESS OF THE SUCCESSFUL BIDDER	M/S. AJJ ENTERPRISES Office No, 12 Ground Floor, Beaumont Plaza, Beaumont Road Civil Line Near P.I.D.C Building Karachi Ph: +92 21 35693738 Mobile: 03219234341-03212695975
➤	RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT (i.e. 1 st , 2 nd , 3 rd EVALUATED BID)	1 st Evaluation Bid
➤	NEED ANALYSIS only the procurement was necessary?)	KPT Authorities is committed to Provide repair / Maintenance of Existing Infrastructure
➤	IN CASE EXTENSION WAS MADE IN RESPONSE TIME, WHAT WERE THE REASONS (Briefly describe)	N/A
➤	WHETHER NAMES OF THE BIDDERS AND THEIR PRICES WERE READ OUT AT THE TIME OF OPENING OF BIDS	YES
➤	DATE OF CONTRACT SIGNING (Attach a copy of agreement)	05-07-2023
➤	CONTRACT AWARD PRICE	Rs. 4,770,085.95
➤	WHETHER COPY OF EVALUATION REPORT GIVEN TO ALL BIDDERS (Attach copy of the bid evaluation report)	Bid Evaluation Report under PPRA Rule-35 attached EV No. <u>EV50901</u>
➤	ANY COMPLAINTS RECEIVED (If yes result thereof)	NO
➤	ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS (If yes give details)	NO
➤	DEVIATION FROM QUALIFICATION CRITERIA (If yes give details)	NO
➤	SPECIAL CONDITIONS, IF Any (Give Brief Description)	N/A


**Executive Engineer (W)
Engineering Department
Karachi Port Trust**

533729



NBP-0007-2305250002400995

GoS-KHI-A0BBB4960BDF4C09

Non-Judicial

Rs 16,696/-

Description	: Contract - 15(a)
Principal	: M/s AJJ Enterprises [31723578]
Contractor	: M/s AJJ Enterprises [31723578]
Applicant	: Muhammad Akmal [42511-09-8883-9]
Stamp Duty Paid by	: M/s AJJ Enterprises [31723578]
Issue Date	: 25-May-2023, 02:24:50 PM
Paid Through Challan	: 202310C6113AECOD
Amount in Words	: Sixteen Thousand Six Hundred and Ninety Six Rupees Only



Please write below this line

Agreement

THIS AGREEMENT made the _____ day of _____ 2021

Between the board of trustees of the port of Karachi incorporated under the Karachi Port Trust Act VI of 1886 as amended from time to time (hereinafter called the "Board") of the one part and M/s. Ajj Enterprises of Office No, 12 Ground Floor, Beaumont Plaza, Beaumont Road Civil Line Near P.I.D.C Building Karachi. (hereinafter called the "Contractor") of the other part WHEREAS the Board is desirous that certain works should be constructed.

VIZ CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 BATHROOMS AT TPX AREAS, KARACHI. (Sanctioned Amount of Rs. 4,770,085.95 (Rupees Four Million Seven Hundred Seventy Thousand Eighty Five & Ninety Five Paisa Only) and has accepted a Tender by the Contractor for the construction completion and maintenance of such Works AND WHEREAS the Contractor has already deposited with the Board the sum of Rs. 125,000.00 (in words Rupees One Hundred Twenty Five Thousand only) being 50% of Total security amount of Rs. 238,600.00 the balance amount of Rs. 113,600.00 Will be deducted through their bill and has given to the Board a lien over sum as security for the due fulfillment of the contract NOW THIS AGREEMENT WITNESSETH as follows:-





1. In this Agreement, works and expressions shall have the same meanings as are respectively assigned to them in the Conditions of contract hereinafter referred to.
2. The following documents which for the purpose of identification have been signed by **Mr. Muhammad Akmal Proprietor** on behalf of the Contractor and by **Mr. Syed Jamil Akhtar XEN(S)** on behalf of Rep of Engineer of the Board of all of which shall be deemed to form and be read and construed as part of this agreement viz:-
 - a. Tender Notice.
 - b. Instructions for Tender.
 - c. The Said Tender with Performa "A" & A-1. alongwith Copy of L.O.I
 - d. The General Conditions of Contract.
 - e. The Specifications Part-I & II
 - f. The Schedule for Quantities with Preamble.
 - g. The Drawings No. 12840 Dt:-25-11-202
3. In consideration of the payments to be made by the Board to the Contractor as hereinafter mentioned the Contractor hereby covenants with the Board to construct complete and maintain the work in conformity in all respects with the provisions of the Contract.
4. The Board hereby covenants to pay the Contractor in consideration of the construction, completion, and maintenance of the Works the Contract price in the manner prescribed by the Contract.
5. **IN WITNESS WHERE OF** the parties hereto have hereunto set their respective hands and seals the day and year first above written.

SIGNED, AND DELIVERED BY THE

Chairman and two Trustees on behalf of the Board of Trustees of the Port of Karachi

Signed by
In the Presence of




22/11/23
General Manager (CW)
CNIC # 42101-729220-3


Chairman, Karachi Port Trust
CNIC #

Singed by

In the presence of

Secretary K.P.T


 Trustee
 Trustee

And

Signed and Delivered By the With named Contractor M/s. Ajj Enterprises Through their Proprietor Mr. Muhammad Akmal

Signed by


In the presence of

1. Mr. 
CNIC # 42201-7778728-7

Sig



Contractor
Mr. Muhammad Akmal Proprietor
CNIC # 42301-0948883-9

2. Mr. 
CNIC # 42201-0774889-5

Sig





KARACHI PORT TRUST
Gateway to Pakistan
A Great Heritage - A Vibrant Future
TENDER NOTICE

Handwritten notes: 30/11/23, 75 2/3, and other scribbles.

عزم عالی بنان شاد رہے پاکستان

KARACHI PORT TRUST
Gateway to Pakistan
A Great Heritage - A Vibrant Future
TENDER NOTICE
Engineering Department

Tenders are invited by the Chief Engineer KPT, under PPRA Rule 56 (a) from Bidders registered with Government, Semi Governmental Department / Organizations or with any reputable client for the following work. All interested firms who possess experience in the relevant field may obtain the tender documents available on the downloaded version at KPT, PPRA & MOMA Websites.

NAME & SCOPE OF WORK	DATE & TIME OF RECEIPT AND OPENING OF TENDER
CONSTRUCTION OF TWO NUMBER SITTING ROOMS WITH 05 BATHROOMS AT EX AREAS, KARACHI	30-01-2023 Receipt at 11:00 HRS & Opening at 11:33 HRS
The work mainly comprises of: • Foundation Works • RCC Work • Brick Masonry Works • Plaster Works • Painting / Coating Works Tie flooring • Construction Pre-Cast Beam & Pre-Cast slab Roof system. • External services according overhead tank & underground tank, electric lines, sewage pit, drain, sewerage line. • Electrification works for rooms and bathrooms. • Other Aided Work	Tender Fee Rs. 2,250/- (Non Refundable)
Bid Security Amount Rs. 125,000/- (Rupees One Hundred Twenty Five Thousand Only) (Cash) (Refundable) in form of Pay Order in the favour of Chief Accounts Officer (KPT)	

- The intending Bidders must be registered with the Pakistan Engineering Council in Category G-0 and above with sponsored code PE-10, valid on the date of opening of tender.
- The intending bidders may visit KPT / PPRA & MOMA Websites and may Download the Tender Documents. The Prescribed Tender Fees amounting to Rs. 2,250/- and the Bid Security of the work which is Rs. 125,000/- (fixed) will be admitted in separate envelopes alongwith the Bid at the time of submission of tender in Shape of any Orders, in favour of Chief Accounts Officer (KPT).
- The Mandatory requirements to be fulfilled are as follows:-
 - Copy of latest Valid NTN, SRB Certificate.
 - Copy of Online Tax Verification (fresh copy of ATN).
 - Updated Company Profile.
 - Copy of Valid PEC Registration Certificate.
- Always that the firm is not defaulter in Income Tax department nor blacklisted by any Organization.
 - In case of companies and firms, last three years Audited Financial Statements are to be provided showing minimum average turnover of Rs. 4.0 Million.
 - In case of individuals - last three years tax returns filed with FBR and its provided showing minimum turnover of Rs. 4.0 Million on average for three years.
- Firm having experience of similar Building Works; work not less than Rs. 4.0 (M) in last ten years for atleast 07 works.
- Only the FBR & SRB Registered Bidders are eligible for bidding. Dealer has to quote their rates exclusive of all Govt. Taxes as applicable to per Standard Format.
- The Bidding will take place in the Conference Room of the Civil Engineering Department, 2nd floor KPT Head Office, Karachi on given date & time.
- The tender must read the instructions contained in Part-16 carefully especially the Para 2 in its full letter & Spirit.
- The Bidders are not allowed to bid or propose at any time prior to the acceptance of a Bid or Proposal. The KPT shall upon request communicate to any supplier or contractor who submitted a Bid or Proposal, the grounds for its rejection of all Bids or proposals, but is not required to justify those grounds.

CHIEF ENGINEER
KPT Head Office Building,
Edujee Dinshaw Road, Karachi-74000,
UAN 111-KPT-111 Ph: 99214318 Fax: 99214329-30,
Web site: www.kpt.gov.pk PPRA Web site address:
www.ppra.org.pk



FD (K) No. 1838/22

Daily 92 News
Dated: 08-01-2023

KARACHI PORT TRUST
Gateway to Pakistan
A Great Heritage - A Vibrant Future
TENDER NOTICE
Engineering Department

Tenders are invited by the Chief Engineer KPT, under PPRA Rule 56 (a) from Bidders registered with Government, Semi Governmental Department / Organizations or with any reputable client for the following work. All interested firms who possess experience in the relevant field may obtain the tender documents available on the downloaded version at KPT, PPRA & MOMA Websites.

NAME & SCOPE OF WORK	DATE & TIME OF RECEIPT AND OPENING OF TENDER
CONSTRUCTION OF TWO NUMBER SITTING ROOMS WITH 05 BATHROOMS AT EX AREAS, KARACHI	30-01-2023 Receipt at 11:00 HRS Opening at 11:33 HRS
The work mainly comprises of: • Foundation Works • RCC Work • Brick Masonry Works • Plaster Works • Painting / Coating Works • Tie flooring • Construction Pre-Cast Beam & Pre-Cast slab Roof system. • External services according overhead tank & underground tank, electric lines, sewage pit, drain, sewerage line. • Electrification works for rooms and bathrooms. • Other Aided Work	Tender Fee Rs. 2,250/- (Non Refundable)
Bid Security Amount Rs. 125,000/- (Rupees One Hundred Twenty Five Thousand Only) (Cash) (Refundable) in form of Pay Order in the favour of Chief Accounts Officer (KPT)	

- The intending Bidders must be registered with the Pakistan Engineering Council in Category G-0 and above with sponsored code PE-10, valid on the date of opening of tender.
- The intending bidders may visit KPT / PPRA & MOMA Websites and may Download the Tender Documents. The Prescribed Tender Fees amounting to Rs. 2,250/- and the Bid Security of the work which is Rs. 125,000/- (fixed) will be admitted in separate envelopes alongwith the Bid at the time of submission of tender in Shape of any Orders, in favour of Chief Accounts Officer (KPT).
- The Mandatory requirements to be fulfilled are as follows:-
 - Copy of latest Valid NTN, SRB Certificate.
 - Copy of Online Tax Verification (fresh copy of ATN).
 - Updated Company Profile.
 - Copy of Valid PEC Registration Certificate.
- Always that the firm is not defaulter in Income Tax department nor blacklisted by any Organization.
 - In case of companies and firms, last three years Audited Financial Statements are to be provided showing minimum average turnover of Rs. 4.0 Million.
 - In case of individuals - last three years tax returns filed with FBR and its provided showing minimum turnover of Rs. 4.0 Million on average for three years.
- Firm having experience of similar Building Works; work not less than Rs. 4.0 (M) in last ten years for atleast 07 works.
- Only the FBR & SRB Registered Bidders are eligible for bidding. Dealer has to quote their rates exclusive of all Govt. Taxes as applicable to per Standard Format.
- The Bidding will take place in the Conference Room of the Civil Engineering Department, 2nd floor KPT Head Office, Karachi on given date & time.
- The tender must read the instructions contained in Part-16 carefully especially the Para 2 in its full letter & Spirit.
- The Bidders are not allowed to bid or propose at any time prior to the acceptance of a Bid or Proposal. The KPT shall upon request communicate to any supplier or contractor who submitted a Bid or Proposal, the grounds for its rejection of all Bids or proposals, but is not required to justify those grounds.

CHIEF ENGINEER
KPT Head Office Building,
Edujee Dinshaw Road, Karachi-74000,
UAN 111-KPT-111 Ph: 99214318 Fax: 99214329-30,
Web site: www.kpt.gov.pk
PPRA web site address: www.ppra.org.pk



**KARACHI PORT TRUST
ENGINEERING DEPARTMENT**

**DOCUMENTS TO
BE RETURNED**

THE TENDER

(Tenderers are required to fill in the blank spaces in this Tender Form and this attached Proforma "A")

To,

**The Chief Engineer,
Karachi Port Trust,
Karachi (Pakistan)**

Handwritten: 30/1/23, 2/3 (circled), 30/1/23, 30/1/23

Description of Work : CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA.

- Having examined the **Drawings** General Conditions of the Contract Special Conditions of Contract (if any) Specification and Bill of Quantities for the construction of the above named-works, we the undersigned offer to construct complete and maintain the whole of the said works in conformity with the said Drawings. General Conditions of Contract. ~~Special Conditions of contract (if any), Specification and Bill of Quantities for the sum of~~ Rupees fourty three (04) Lakhs four thousand Eight hundred Eighty seven and paise Rs. 4348878.45) or such other sums as may be **ascertained** with the said Conditions.
- If undertake if our Tender is accepted in whole or in part to commence the work within **07 days** of receipt of the Engineer's order to commence and to complete and deliver the whole of the Works comprised in the Contract within (**06 Months**) calculated from the last day of aforesaid period in which the works are to be commenced
- If our Tender is accepted in Whole or in **part we** will furnish a Security Deposit for due performance of the Contract in accordance with Clause 9 of the General Conditions of Contract.
- We agree to abide by this tender for a period of (**180 Days**) from the date fixed for receiving the same and it shall remain binding upon us and may be accepted at any time before expiration of that period.
- Unless and until a formal Agreement is prepared and executed this tender, together with your written acceptance thereof, shall constitute a binding Contract between us.
- We understand that you are not bound to accept the lowest or any Tender you may receive and accept any Tender in part or in whole.



7.

We further agree to pay all cost towards the execution of the Contract Agreement including the cost of stamps.

8.

We agree that should we withdraw the offer within the aforesaid period or fail to execute the formal

contract Agreement and / or make the required Security Deposit the Board of Trustees of the Karachi Port Trust shall be at liberty at their absolute discretion to appropriate our (Bid Security Amount Rs. 125,000.00 Fix) either as agreed liquidated damages without any proof whatsoever of the extent of such damage or on account reserving to themselves the right to recover from us any further loss or expenses to which they may have been put directly or indirectly by reason of any failure on our parts as aforesaid.

9.

We enclose a pay order for Rs. 125,000 + 2250/- as Bid Security within favour of the Chief Accounts

Officer, Karachi Port Trust and hold his receipt No. 16566603-2 dated 27/01/2023

10

We agree to maintain the work in good order for a period of 12 Months from the date of its

Completion

Date: 30/01/2023

TENDERER

Place:

Karachi



(FULL SIGNATURE)

Signed by Mr.

Muhammad Akmal

for and on behalf of

Messrs

A.J.C. Enterprises

Address

Shop No 12 Beamoul-Plaza Near P.I.D.C Building Karachi

Executive Engineer (W)
Engineering Department
Karachi Port Trust

2



Original P.O. No. Enclosed.

- ① P.O No. 16566603 Dt. 27/01/23 Rs. 125,000/-
- ② P.O No. 16566602 Dt. 27/01/23 Rs. 2250/-



KARACHI PORT TRUST

ENGINEERING DEPARTMENT

PROFORMA "A"
(To be submitted with the Tender)

Handwritten notes:
2/8
30/1/23
30/1/23

Particulars	Details
1. Experience as a Contractor	11 years
2. Works carried out in the past with detailed cost particulars and the year in-which they were undertaken etc.	2021-2022 72 million
3. Banker reference regarding Financial status	HMB
4. Whether registered with any Other Department or Organization? if so, give details.	PEC - C-5

Handwritten note:
39-01-23

Signature:
Executive Engineer (W)
Engineering Department
Karachi Port Trust



PROFORMA "A"

2/3
30/1/23

Particulars	Details
5. Plant and equipment in possession (Give details with Cost)	On Having Bases
6. Technical personnel employed: give names and other details	Profile Submitted
7. Is your firm registered?	Yes
8. State capital of your firm?	5.5 million.
9. Detail of Income Tax Sales Tax Registration etc.	3172357-8
10. Number of years of actual work carried out in Pakistan	11 year's
11. Attach attested copies of certificates of past work of the same nature carried out as that in this Tender.	Profile Submitted



Date 30/01/2023
Place Karachi



SIGNATURE OF TENDERER

Signed by Mr. Muhammad Akmal
For and on behalf of Ajiz Enterprises



KARACHI PORT TRUST

ENGINEERING DEPARTMENT PROFORMA "A-1"

COMPOSITION & PARTICULARS OF THE TENDERING FIRM
(To be submitted with the Tender)

Handwritten signature and date: 30/1/23

Handwritten notes: 30/1/23, 30/1/23, and a circled fraction 2/3

Particulars	Details
NOTE: The information relevant to the tender should be given below, failing which the tender will not be considered.	
1. in case of Sole proprietorship Concern.	<p><i>Sole Proprietor</i></p> <p><i>Office No 12 Beaman Plaza Near P.I.D.C Building Karachi</i></p> <p><i>F-32 Azam Plaza Badshahi Road Garden west Karachi</i></p>
a) Business Address. b) Residential Address.	
2. In case of Partnership Concern.	
a) Name of the Partners with their Residential Address.	<i>N/A</i>
b) Partnership Deed & Certificate of Registration. (Attach Certified Copies)	
3. In Case of Private Ltd. Company	
a) Name of all Directors with their Residential Address.	<i>N/A</i>
b) Memorandum & Articles of association of the company & Certificate of incorporation. (Attach Printed, Certified Copies)	
4. in Case of Public Ltd. Company Memorandum and Articles of Association and Certificate, of incorporation (Attach Printed, Certified Copy)	<i>N/A</i>

In submitting the above particular to further bind ourselves of furnishing to the K.P.T. any further changes our particulars and composition of our firm.

We clearly understand that failure we comply with the above or for submitting incorrect or inaccurate information, will render our tender invalid.



*Executive Engineer (EP)
Engineering Department
Karachi Port Trust*



SIGNATURE & SEAL OF THE TENDERER

Signed By Mr. *Muhammad Akmal*
for, & on behalf of *D.J. Enterprises*

24 November 2022



**KARACHI PORT TRUST
ENGINEERING DEPARTMENT**

**DOCUMENTS TO
BE RETURNED**

Handwritten: 30/11/22
Handwritten: 30/11

Handwritten: 2/3

Handwritten: 30/11/22

**NAME OF WORK: CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH
05 WASHROOMS AT TPX AREA.**

S.No	Description of Work	Unit	Rate	Quantity	Amount(Rs.)
------	---------------------	------	------	----------	-------------

Notes:-

- a) After the completion of the work the contractor is required to clear away and remove from the site all construction plants, surplus material, rubbish, debris and temporary works of every kind etc. to the entire satisfaction of the Engineer. It may be noted that Contractors' account will not be finalized till such time a certificate to this effect is obtained from Executive Engineer and submitted to the Chief Engineer for his information.
- b) The Contractor must ensure that the dismantled materials should be disposed in accordance with safety standards fixed by the civic agencies and specified environmental protection rules.
- c) Debris dismantled materials, rubbish etc. should be disposed in such a way that it should not cause any pollution and shall not be source of harm to public.
- d) The tenderer must fill all the pages of Performa "A" & A-1" of tender documents, and ensure enclosing of the pay order for bid Security amount Rs 125,000.00 Fix
- e) The tenderers are advised to avoid cutting / over writing in B.O.Q. In case any cutting / over writing it should be properly re-write, sign and stamp otherwise, the tenders may not be considered.
- f) The (Contractor Tech Representative) is bound to visit the plan monthly & give satisfactory report after checking the plan or he is bound to visit on the call of the Engineer Incharge as & under required.
- g) **"Only the FBR & SRB Registered Contractors are eligible for bidding, Contractor has to quote their rates inclusive of all Govt. Taxes".**

Handwritten: [Signature]
**Executive Engineer (W)
Engineering Department
Karachi Port Trust**



CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA.

2/3

30/1/20

130/1/20

Item description

EXCAVATION OF ANY KIND OF FOUNDATIONS, DRAINS, TRENCHES, EMBANKMENTS AREA SHAFTS, WELLS, INDEPENDENT HOLES ETC UP TO REQUIRED DEPTH AND 6FT BY ANY MEANS (MANUALLY OR MECHANICALLY) AND BACK FILLING THE EXCAVATED SPOIL WITH SAME MATERIAL CONSOLIDATION, WATERING AND COMPACTION IN LAYERS COMPLETE INCLUDING COST OF TIMBERING AND DEWATERING (IF REQUIRED) AND DISPOSE OFF SURPLUS SPOIL OUTSIDE NOT LIMIT OR AS DIRECTED BY THE ENGINEER IN CHARGE. PROVIDING AND LAYING STONE BALLAST OF APPROVED GRADE AND QUALITY AND THICKNESS MESH UNDER WATER 1/3 WATERING AND CONSOLIDATION ETC OR AS DIRECTED BY ENGINEER IN CHARGE.

PROVIDING AND LAYING 75 MM (3") THICK BLINDING BED OF 1:4:8 CEMENT CONCRETE USING GRADED CRUSH 20 MM AND DOWN GAUGE IN FOUNDATION ABOVE TIDAL LEVEL INCLUDING LEVELING, COMPACTING AND CURING ETC., COMPLETE.

PROVIDING AND LAYING REINFORCED CEMENT CONCRETE USING SCREENED GRADED BAJRI 20 MM (3/4") AND DOWN GAUGE HAVING A MINIMUM WORKING CUBE CRUSHING STRENGTH OF 3000 LBS. PER SQ. INCH (CYLINDRICAL MOULD) AFTER 28 DAYS WITH A MIX NOT LEANER THAN 1:2:4 IN FOUNDATIONS, COLUMN, BEAMS, LINTELS, ROOF SLAB, CHAJJA, WALLS STAIRCASE, ETC., OF REQUIRED SHAPE AND DESIGN INCLUDING FORM WORK AND ITS REMOVAL, COMPACTING AND CURING ETC. COMPLETE, BUT EXCLUDING THE COST OF REINFORCEMENT AT ANY HEIGHT ANY FLOOR.

PROVIDING AND LAYING HARD GRADE RIBBED TOR STEEL (MINIMUM STRENGTH 60,000 PSI) REINFORCEMENT BARS WITH AND INCLUDING THE COST OF STRAIGHTENING, CUTTING, BENDING, BINDING, WASTAGE, PLACING IN POSITION, M.S. CHAIRS, TYING WITH BIND NG WIRE OF 14 SWG, COST OF CHAIRS AND WIRES ETC. IN ALL KIND OF RCC WORK.

PROVIDING AND LAYING 3" THICK DAMP PROOF COURSE (DPC) USING CEMENT CONCRETE 1:2:4 USING CRUSHED OR GRADED SCREENED OF 3/4" AND DOWN GAUGE MIXED WITH ANY APPROVED

WATER PROOFING AGENT @ 5LBS/BAGS OF CEMENT INCLUDING COMPACTION CURING FROM WORK (IF REQUIRED) AND IS REMOVAL ETC COMPLETE AS DIRECTED

BACK FILLING EARTH OR SAND USING AVAILABLE MATERIAL AT SITE IN FOUNDATION, PLINTH OR UNDER FLOOR ETC INCLUDING BREAKING CLOTS, DRESSING, WATERING, CONSOLIDATING, COMPACTION, TO REQUIRED PROFILE AND BY RAMMING IN

Unit	Rate	Rate in Words	Quantity	Amount
PER CUM	1400/-	One thousand Four hundred only	55.00	77,000/-
PER CUM	1500/-	One thousand five hundred only	17.00	25,500/-
PER CUM	5000/-	Five thousand only	6.00	30,000/-
PER CUM	9000/-	Nine thousand only	8.00	72,000/-
PER KG	300/-	Three hundred only	900.00	2,70,000/-
PER SQM	4000/-	Four thousand only	5.00	20,000/-
PER CUM	8000/-	One thousand only	35.00	35,000/-



CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA.

Plan #

2/3

30/11/22

Dated :

Item description

PROVIDING AND LAYING 1:3:6 CEMENT CONCRETE SOLID BLOCK MASONRY AS IN WALLS AND PILLARS USING GRADED SCREENED BAJRI 20 MM (3/4") AND DOWN GAUGE SET IN 1:4 CEMENT MORTAR INCLUDING SCAFFOLDING RAKING OUT JOINTS AND CURING ETC., COMPLETE,

PREPARE SURFACE AND APPLYING 1/2": 3/4": THICK CEMENT SAND PLASTER AT ANY HEIGHT ANY FLOOR OF RATIO 1:4, FINISHED SMOOTH INCLUDING CURING, SCAFFOLDING, CORNICES, EDGES ALL AS SPECIFIED AND DIRECTED.

PROVIDING AND LAYING 75 MM (3") THICK PLAIN CEMENT CONCRETE OF RATIO 1:2:4 CEMENT CONCRETE USING GRADED CRUSH 20MM (3/4") AND DOWN GAUGE IN PANELS AS LAID IN FLOOR, SCREED, UNDER FLOOR OR LIKE INCLUDING LEVELING, COMPACTING AND CURING ETC., COMPLETE.

PROVIDING AND FIXING OF PRECAST ROOF SLAB INCLUDING OF PRE CAST RCC GARDERS(5' X 12"), 1 1/2" THICK PRE CAST SLAB AND OF ALL TRANSPORT, LIFTING, FIXING IN POSITION JOINTING GROUTING WITH CEMENT SAND MORTER OF RATIO 1:4 EMBEDDING IN POSITION AT ANY HEIGHT ANY FLOOR ALL AS SPECIFIED AND AS PER THE DIRECTION OF ENGINEER INCHARGE PROVIDING AND LAYING 2" THICK CEMENT CONCRETE OF RATIO 1:2:4 USING 1/4" DIA BAR @ 8"C/C B/W (STEEL PAID IN HEAD IN SERAIL # 05) AND USING GRADED CRUSH 16MM (1/2") AND DOWN GAUGE IN PANELS AS LAID IN FLOOR, SCREED, UNDER FLOOR OR LIKE INCLUDING LEVELING, COMPACTING AND CURING ETC., COMPLETE AS PER THE DIRECTION OF ENGINEER INCHARGE (INCLUDING FORM WORK)

PROVIDING AND LAYING BITUMINOUS WATER PROOFING FELT 3X PLY ON ROOF TOP WITH ADHESIVE NO. 70 @ OF 10 LBS/100 SFT DILUTED WITH 13% OF SOLVENT LIKE KEROSENE OIL ETC., INCLUDING THE COST OF OVER LAPS, CLEANING, HACKING OUT OLD, AND SCRAPPING THE SURFACE BY WIRE BRUSHING BEFORE APPLYING THE ADHESIVE AND FELT ETC COMPLETE AS PER SPECIFICATION OR AS RECOMMENDED BY THE MANUFACTURER AT ANY HEIGHT ANY FLOOR

PROVIDING AND LAYING 13MM TERRAZZO FLOOR AND DADO USING MARBLE CHIPS (1:2) WITH WHITE/ COLOURED CEMENT, INCLUDING CUTTING AND RUBBING ETC OR AS DIRECTED BY ENGINEER INCHARGE.

PROVIDING AND FIXING 1 1/2" THICK BEST QUALITY PARTIAL WOOD DOORS, WINDOWS AND VENTILATORS SINGLE/ DOUBLE LEAF, FULLY/ PARTIALLY paneled & PARTIALLY PLAIN GLAZED WITH APPROVED BRASS FITTINGS (MONGERY) AND REQUIRED PARTIAL WOOD FRAME OF SIZE (N.EXEC 14 SQ. INCH) INCLUDING WOODEN CLEATS & STOPPERS, BEADING ETC COMPLETE, FRAME HANGING IN POSITION, FIXED ON WALLS WITH HOLD FASTS ETC OR AS

Unit	Rate	Quantity	Amount
PER CUM	13000/-	79.00	1027,000/-
PER SQM	600/-	435.00	261,000/-
PER CUM	6000/-	7.00	42,000/-
PER SQM	4000/-	82.00	328,000/-
PER SQM	1000/-	82.00	82,000/-
PER SQM	700/-	82.00	57,400/-
PER SQM	2000/-	38.00	76,000/-
PER SQM	8000/-	25.00	200,000/-



CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA.

Plan #

Dated :

Item description

PREPARE SURFACE AND APPLYING 2X COATS OF OIL BOUND DISTEMPER APPROVED MAKE AND SHADE INCLUDING SCRAPING SAND PAPERING DUSTING AND FILLING THE HOLES, CRACKS AND INEQUALITIES IF ANY AT ANY HEIGHT AND IN ANY FLOOR 1/3. REMOVING RUBBISH ETC., OUTSIDE K.P.T. LIMIT.. PREPARE SURFACE AND APPLYING 2X COATS OF SYNTHETIC ENAMEL PAINT APPROVED MAKE AND SHADE INCLUDING SCRAPING SAND PAPERING DUSTING AND FILLING THE HOLES, CRACKS AND INEQUALITIES IF ANY AT ANY HEIGHT AND IN ANY FLOOR 1/3. REMOVING RUBBISH ETC., OUTSIDE K.P.T. LIMIT..(IRON, WOOD AND MASONRY) SUPPLY AND FIX, GYPSUM CEILING 600MM X 600MM X 7.5MM THICK, INCL. ALUMINIUM TEE & ANGLE, 25MM X 25MM X 1MM, INCLUDING HANGER CLIPS, JOINTING CLIPS AND 14 SWG, GI WIRE ETC, COMPLETE.

PROVIDING AND FIXING OF 3/4" DIA UPVC PIPE AND SPECIALS INCLUDING EXCAVATION ,CUTTING OF WALL, GROUND ETC FIX WITH ALL ACCESSORIES LIKE TO LIKE "T", BEND,SOCKETS,ELBOWS,"Y", UNIONS ETC COMPLETE AND USE OF BOND ADHESIVE ALL BEST APPROVED QUALITY AND MAKE INCLUDING COST OF MAKING GOOD THE DISTURB SURFACES ON LIKE TO LIKE BASES FIXED AT ANY HEIGHT ANY SURFACE AS DIRECTED BY ENGINEER / INCHARGE.

PROVIDING AND FIXING OF 1/2" DIA UPVC PIPE AND SPECIALS INCLUDING EXCAVATION / CUTTING OF WALL, GROUND ETC AND FIX WITH ALL ACCESSORIES LIKE T, BENDS, SOCKETS, ELBOWS, UNIONS ETC COMPLETE AND USE OF BOND ADHESIVE ALL OF BEST APPROVED QUALITY AND MAKE INCLUDING COST OF MAKING GOOD THE DISTURB SURFACES ON LIKE TO LIKE BASIS, FIXED AT ANY HEIGHT ANY SURFACE.

PROVIDING AND FIXING OF BEST QUALITY OF APPROVED MAKE AND QUALITY (MASTER OR EQUIVALENT) 07 PIECES BATH ACCESSORIES SET, FANCY TYPE GLASS TYPE (ECONOMY MODEL) FIXED COMPLETE

PROVIDING AND FIXING EASTERN TYPE WHITE / LIGHT COLOR GLAZED WARE WC INCLUDING 13 LITER FLUSHING CISTERN LOW DOWN PLASTIC INCLUDING THE COST OF 4x DIA BRASS THIMBLE, MAKING CONNECTION WITH THE WATER AND SEWERAGE MAIN ETC ALL AS SPECIFIED AND DIRECTED. (EXCLUDING THE COST OF T-STOP) COCK, STOP COCK, MUSLIM SHOWER, ETC) PROVIDING AND FIXING WASH HAND BASIN 25" X 18" INCLUDING PEDESTAL WHITE / LIGHT COLOR GLAZED WARE INCLUDING THE COST OF ALL NECESSARY FITTINGS LIKE WASTE COUPLING, WASTE PIPE, CONNECTIONS, KIT SCREWS) WROUGHT IRON BRACKETS & MAKING CONNECTION WITH THE WATER AND SEWERAGE MAIN ETC ALL AS SPECIFIED AND DIRECTED. (EXCLUDING THE COST OF T-STOP COCK, STOP COCK, MIXER,

Unit	Rate	Quantity	Amount
PER SQM	200/- Two Handed only	435.00	87,000/-
PER SQM	200/- Two Handed only	50.00	10,000/-
PER SQM	1200/- One thousand two Handed only	45.00	54,000/-
R/M	500/- Ene Handed only	90.00	45,000/-
PER SQM	5000/- Ene Handed only	50.00	250,000/-
EACH	8000/- Eight thousand only	5.00	40,000/-
EACH	8000/- Eight thousand only	5.00	40,000/-
EACH	8000/- Eight thousand only	5.00	40,000/-



U. Q. ITEMS

Engineering Department

Dated : *****

CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT 1PX AREA.

Plan #

Dated :

Item description

PROVIDING AND FIXING BATHROOM/ WASHROOM SET FIXTURE OF APPROVED QUALITY MASTER MAKE OR EQUIVALENT CONSISTING OF BIBCOCKS, MIXER, O.H SHOWER SET, STOP COCKS, FOR O.H SHOWER, EASTREN W.C. COMMOD, HAND WASH BASIN & LOOKING MIRROR, SOAP DISH, ETC.
 COMPLETE) FIXING IN PROPER POSITION COMPLETE AS DIRECTED PROVIDING AND LAYING 6MM THICK WHITE / COLORED CERAMIC TILES GLAZED / MATT NOT EXEC. 144 SQ INCH FINE DRESSED ON THE SURFACE WITHOUT GRINDING LAY OVER 1/4" THICK CEMENT MORTAR OF RATIO 1:2, AND IN DADOS & SKIRTING LAID OVER 1/2" THICK BASE OF CEMENT MORTAR 1:3 SETTING TILES IN SLURRY OF GREY CEMENT, JOINTING AND WASHING THE TILES WITH WHITE / COLORED CEMENT SLURRY ALL AS SPECIFIED OR USE OF BOND MORTAR INSTEAD OF CEMENT MORTAR WHICH EVER REQUIRED.

(EXTERNAL SERVICES)
 CONSTRUCTION OF UNDER GROUND RCC WATER TANK OF CAPACITY 1350 GALLON INCLUDING EXCAVATION RCC WALLS, BOTTOM & TOP SLAB USING 3/8" BAR REINFORCEMENT @ 8" C/C BOTH WAYS IN SLAB AND 3/8" DIA BAR @ 6" C/C IN BOTH WAYS IN SLAB & FOUNDATION COMPLETE (AS PER DRAWING ATTACHED) COST OF REINFORCEMENT INCLUDED.
 CONSTRUCTION OF SEPTIC TANK SIZE (9'X5'X5'), 9" THICK OUTER AND 4" THICK PARTITION MASONRY WALLS, SLAB AND FOUNDATION THICKNESS IS 6" THICK 1/E USING 3/8" DIA BAR @ 8" C/C, B/W DOUBLE MESH INCLUDING EXCAVATION, STONE SOLING, PCC (1:4:8), SHUTTERING, REINFORCEMENT CONCRETE (1:2:4), PLASTER, TERRAZZO, MAIN HOLE COVER (18"X18"), BACK FILLING COMPLETE AS PER SATISFACTION OF ENGINEER INCHARGE.
 (COST OF REINFORCEMENT INCLUDED.)
 CONSTRUCTION OF SOAKAGE PIT HAVING 4' DIA & THE REQUIRED DEPTH 1/E 3' BELOW THE LEVEL OF GROUND WATER TABLE, COMPLETE AS PER DRAWING (ATTACHED) AND AS DIRECTED BY ENGINEER INCHARGE.

CONSTRUCTION OF MAIN HOLE COMPLETE RECTANGULAR / CIRCULAR SIZE (2' X2' INNER), 6" THICK WALLS CC SOLID BLOCK MASONARY SET IN CM 1:2 AND PLASTER AS DESCRIBE NOT EXCEED 3' DEEP FROM INVERT TO SURFACE OF COVER INCLUDING EXCAVATION, BED CONCRETE, 4" THICK RCC SLAB WITH 18" X 18" RCC MAIN HOLE COVER WITH ANGLE IRON FRAME, ALL AS SPECIFIED AND DIRECTED
 PROVIDING AND FIXING OF 4" DIA UPVC PIPE AND SPECIALS INCLUDING EXCAVATION, CUTTING OF WALL, GROUND TO FIX WITH ALL ACCESSORIES LIKE TO LIKE "T", BEND, SOCKETS, ELBOWS, Y, UNIONS ETC COMPLETE AND USE OF BOND ADHESIVE ALL BEST APPROVED QUALITY AND MAKE

Unit	Rate	Quantity	Amount
EACH	8800/-	5.00	44,000/-
PER SQM	2900/-	90.00	261,000
1 JOB	150,000/-	1.00	150,000/-
1 JOB	100,000/-	1.00	100,000/-
1 JOB	40,000/-	1.00	40,000/-
EACH	8,000/-	10.00	80,000/-
	160,000/-	160.00	160,000/-



J. Q. ITEMS

Engineering Department

Dated : *****

CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA.

Plan #

Dated :

Item description

PROVIDING AND FIXING OF FIBER GLASS WATER TANK CAPACITY OF 500 GALLONS (FOR RESERVE WATER), INCLUDING THE UPLIFTING JOINTING AND CONNECTING FOR WATER SUPPLY IN LET / OUT LET.

PROVIDING AND FIXING OF FIBER GLASS WATER TANK CAPACITY OF 250 GALLONS, INCLUDING THE UPLIFTING JOINTING AND CONNECTING FOR WATER SUPPLY IN LET / OUT LET.

(ELECTRICAL ITEMS)

WIRING FOR LIGHT, FAN, BELL ETC WITH 2 X 3/029 + 1 X 1.5 MM² GREEN AS E.C.C, PVC INSTALLED COPPER WIRE MANUFACTURED BY PSQCA CERTIFIED COMPANIES CONCEALED IN WALL THAN LAYING PVC PIPE BY PSQCA CERTIFIED COMPANIES WITH PVC ACCESSORIES LIKE BEND, SOCKET, L-BOW, J-BOX ETC, INCLUDING PROVIDING AND FIXING THE APPROVED BOARD CONCEALED CONCEALED OR SURFACE TYPE WITH FUNTIMA MAKE TOP BOARD SHEET NO. OF HOLES REQUIRED AS PER SITE, INCLUDING FIXING 6/10-A, 220/240-V SWITCH PLANO, FUNTIMA MAKE INCLUDING INTERCONNECTION ON BOTH ENDS. A COMPLETE JOB IN ALL RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY KPT)

WIRING FOR LIGHT, FAN, BELL ETC WITH 2 X 3/029 + 1 X 1.5 MM² GREEN AS E.C.C, PVC INSTALLED COPPER WIRE MANUFACTURED BY PSQCA CERTIFIED COMPANIES CONCEALED IN WALL THAN LAYING PVC PIPE BY PSQCA CERTIFIED COMPANIES WITH PVC ACCESSORIES LIKE BEND, SOCKET, L-BOW, J-BOX ETC, INCLUDING PROVIDING AND FIXING THE APPROVED BOARD CONCEALED CONCEALED OR SURFACE TYPE WITH FUNTIMA MAKE TOP BOARD SHEET NO. OF HOLES REQUIRED AS PER SITE, INCLUDING FIXING 5/10-A, 220/240-V SWITCH PLANO, FUNTIMA MAKE INCLUDING INTERCONNECTION ON BOTH ENDS. A COMPLETE JOB IN ALL RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY KPT)

WIRING FOR UNIVERSAL WITH 2 X 7/029 + 1 X 1.5 MM² GREEN AS E.C.C, PVC INSTALLED COPPER WIRE MANUFACTURED BY PSQCA CERTIFIED COMPANIES CONCEALED IN WALL THAN LAYING PVC PIPE BY PSQCA CERTIFIED COMPANIES WITH PVC ACCESSORIES LIKE BEND, SOCKET, L-BOW, J-BOX ETC, INCLUDING FIXING THE APPROVED BOARD CONCEALED OR SURFACE TYPE BOARD WITH 2/3 PINS. 5/6-A, 220/240-V UNIVERSAL SWITCH AND SOCKET COMBINED, FUNTIMA MAKE INCLUDING INTERCONNECTION ON BOTH ENDS. A COMPLETE JOB IN ALL RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY KPT)

WIRING FOR POWER PLUG WITH 2 X 6 MM² GREEN AS E.C.C, PVC INSTALLED COPPER WIRE MANUFACTURED BY PSQCA CERTIFIED COMPANIES CONCEALED IN WALL THAN LAYING PVC PIPE BY

Unit

Quantity

Amount

EACH

1.00

45,000/-

EACH

3.00

10,500/-

POINT

30.00

3,000/-

POINT

10.00

4,500/-

POINT

6.00

3,000/-

2.00

1,900/-

45000/- Forty Five thousand only

35000/- Thirty five thousand only

10000/- One thousand only

4500/- Four thousand fifty only

500/- Five hundred only

950/- Nine hundred fifty only

2/3

20/11/23

[Handwritten signature]



CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA

Plan #

30/11/20
30/11/20

Dated :

Item description

BOARD WITH 3-PIN 30-A, 220/240-V POER PLUG SOCKET.
 PROCELLAIN BASED FUNTINA MAKE INCLUDING
 INTERCONNECTION ON BOTH ENDS. A COMPLETE JOB IN ALL
 RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED
 ITEMS WILL BE PROVIDED BY KPT)

FIXING LED TUBE LIGHT FITTING 2 X 2, 18-W MAKE OSAKA
 COMPLETE REPUTABLE MAKE AS PER APPROVED BY THE ENGINEER.
 A COMPLETE JOB IN ALL RESPECT AS REQUIRE AT SITE.
 (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY
 KPT)

WIRING FOR LIGHT CIRCUIT POINT WITH 2 X 4 MM² GREEN AS
 E.C.C, PVC INSTALLED COPPER WIRE MANUFACTURED BY PSQCA
 CERTIFIED COMPANIES CONCEALED IN WALL THAN LAYING PVC
 PIPE BY PSQCA CERTIFIED COMPANIES WITH PVC ACCESSORIES
 LIKE BEND, SOCKET, L-BOW, J-BOX ETC, INCLUDING
 INTERCONNECTION ON BOTH ENDS. A COMPLETE JOB IN ALL
 RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED
 ITEMS WILL BE PROVIDED BY KPT)

FIXING LED LIGHT FITTING 18-W COMPLETE MAKE OSAKA AS PER
 APPROVED BY THE ENGINEER. A COMPLETE JOB IN ALL RESPECT
 AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED ITEMS
 WILL BE PROVIDED BY KPT)

FIXING LED FLOOD LIGHT FITTING 100 WATTS MAKE OSAKA OR
 EQUIVALENT AS APPROVED BY ENGINEER. (INSTALLATION ONLY,
 REQUIRED ITEMS WILL BE PROVIDED BY KPT)

FIXING THE CEILING FAN 56" SWEEP COMPLETE PAK/MILLAT MAKE
 REQUIRED LENGTH OF DOWN ROD AND 220-VOLTS PIANO TYPE
 DIMMER. A COMPLETE JOB IN ALL RESPECT AS REQUIRED AT SITE.
 (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY
 KPT)

FIXING 8" / 10" PLASTIC BODY OR METAL BODY EXHAUST FAN,
 REPUTABLE MAKE INCLUDING ALL CIVIL WORKS. A COMPLETE JOB
 IN ALL RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY,
 REQUIRED ITEMS WILL BE PROVIDED BY KPT)

INSTALLATION OF D.B OF M.S SHEET WITH FOLLOWING
 ACCESSORIES;
 * M.C.B 20-ASP FUJI / TERASAKI REPUTABLE MAKE = 02-NOS.
 * M.C.B 10-ASP FUJI / TERASAKI REPUTABLE MAKE = 04-NOS.
 * INDICATION LAMP = 03-NOS.
 INCLUDING NEUTRAL STRIP & INTERNAL WIRING. A COMPLETE JOB
 IN ALL RESPECT AS REQUIRED AT SITE.
 (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY
 KPT)

Quantity

Unit

Rate

Amount

2/3

500 1/2 Five Handseel only

1000 1/2 One thousand only

500 1/2 Five Handseel only

500 1/2 Five Handseel only

500 1/2 Five Handseel only

600 1/2 Six Handseel only

2,500 1/2 Twenty thousand only

4.00

2.00

16.00

2.00

4.00

5.00

1.00



J. Q. ITEMS

Engineering Department

Dated: *****

CONSTRUCTION OF TWO NUMBER SITTING ROOM WITH 05 WASHROOMS AT TPX AREA.

Plan #

Dated:

30/1/23
30/1/23

Item description

FIXING THE MONO BLOCK TYPE CENTRIFUGAL PUMP, SINGLE PHASE ON RCC FOUNDATION WITH M.S NUT BOLTS. ALSO SUCTION PIPE OF REQUIRED SIZE WITH ACCESSORIES LIKE CPVC PIPE, BEND, SOCKET, VALVE SOCKET AND BRASS FOOT VALVE. A COMPLETE JOB IN RESPECT AS REQUIRED AT SITE. (INSTALLATION ONLY, REQUIRED ITEMS WILL BE PROVIDED BY KFT)

Unit EACH

Quantity

3.00

Amount

9000/-

3000/- Three thousand only

4020300

TOTAL :	4020300/-	399,3300/-	X
ADD 5% CONTINGENCIES	201015	199,665/-	0 X
NET TOTAL	4221315/-	4192,965/-	X
ADD 13% S.R.B	548,770.95	545,085.45	X
GRAND TOTAL	4770085.95	47,38,050.45	X

[Signature]
Executive Engineer (P)
Engineering Department
Karachi Port Trust

Forty Seven Lac Thirty Eight Thousand fifty and forty five Pasa Only.



collections.
CHECKED
 Rs. 4770085.95
 for 31/01/23



KARACHI PORT TRUST
GATEWAY TO PAKISTAN



TENDER LIST

Closing Date	Opening Date	Description	
30, Jan 2023	30, Jan 2023	Construction of Two Number Sitting Rooms With 6 Bathrooms at Construction of Two Number Sitting Rooms With 6 Bathrooms at TENDER DOCUMENTS. • Type: Repair/Maintenance	0 Downloaded

Public Tenders

View By: All Organizations Sectors

Please Click on image to Download/View.
Only 10 days old tenders from the closing date will be shown.

Organization Name: Karachi Port Trust

Sector Name :

Mechanical/Machinery

Search

Tender No Tender Title

Download Advertised Date Closing Date

Tender No	Tender Title	Download	Advertised Date	Closing Date
TS500170E	Karachi Port Trust, Karachi Construction of Two Number Sitting Rooms With 6 Bathrooms at Construction of Two Number Sitting Rooms With 6 Bathrooms at N/A		13/1/2023	30/1/2023 11:00:00 AM



Monday, May 18, 2023



Home NIP Trainings Public Tenders EPADS Trainings Tender Search Annual Reports Legal Documents

- Home
- Online Query
- Query Reply
- Frequently Asked Questions
- Registration
- PPRA Board
- Downloads (SRO, Manuals, Forms)
- Active Black Listed Firms
- De-Listed Black Listed Firms
- Procurement Planning
- Evaluation Results
- Procurement Contracts
- Tenders Referral Committees
- Misc. Laws and Acts
- Tender Guidelines
- Contact Us

Evaluation Results

Organization Name: Karachi Port Trust

Evaluation No	Evaluation Result Title	Download	Uploaded Date
EV50975	Karachi Port Trust Final Evaluation Maintenance/Repair and Extension of Living Room... E/N-2(71)/ TS504644E		17/5/2023
EV50901	Karachi Port Trust Final Evaluation Construction of Two Number Sitting Rooms.... E/CW-2(583)/ TS500170E		15/5/2023
EV50900	Karachi Port Trust Final Evaluation Demolition of Pilot Pier.... E/CW-2(588)/ TS504378E		15/5/2023
EV50899	Karachi Port Trust Final Evaluation Major Rehabilitation/Replacement of Water... E/CW-28(1390)/ TS501655E		15/5/2023
EV50898	Karachi Port Trust Final Evaluation Cleaning of Underground and Overhead.... E/CW-28(1392)/ TS503137E		15/5/2023
EV50897	Karachi Port Trust Final Evaluation Refurbishment of 8 Dia M.S Fresh.... E/CW-28(1394)/ TS501771E		15/5/2023
EV50654	Karachi Port Trust Final Evaluation Maintenance and Repair to Sacred,,,,, E/CS-2(612)/ TS487814E		5/5/2023
EV50653	Karachi Port Trust Final Evaluation Repairs/Maintenance of Port Safety.... E/CS-2(895)/ TS501306E		5/5/2023
EV50529	Karachi Port Trust Technical Evaluation Rehabilitation of Oil Pier.... E/CS 2(792)/ TS505055E		2/5/2023

